


Technical Progress of the CKM Experiment

Ken Nelson - University of Virginia
on behalf of the CKM Collaboration

*Fermilab PAC
March 28, 2003*



Charged Kaons at the Main Injector

March 29, 2003

A Proposal for a Precision Measurement of the Decay $K^+ \rightarrow \pi^+ \nu \bar{\nu}$ and Other Rare K^+ Processes at Fermilab Using the Main Injector

J. Frank, S. Kettell, R. Strand
Brookhaven National Laboratory, Upton, NY, USA

L. Bellantoni, R. Coleman, P.S. Cooper*, T. R. Kobilarcik, H. Nguyen, E. Ramberg,
R. S. Tschirhart, H. B. White, J. Y. Wu
Fermi National Accelerator Laboratory, Batavia, IL, USA

G. Britvich, V. Burtovoy, A. V. Inyakin, V. Kurshetsov, A. Kushnirenko,
L. G. Landsberg, V. Molchanov, V. Obraztsov, S. I. Petrenko, V. I. Rykalin,
A. Soldatov, M. M. Shapkin, O. G. Tchikilev, D. Vavilov, O. Yushchenko
Institute of High Energy Physics, Serpukhov, Russia

V. Bolotov, S. Laptev, A. Polarush, A. Pastsiak, R. Sirodeev
Institute of Nuclear Research, Troisk, Russia

J. Engelfried, A. Morelos
Instituto de Fisica, Universidad Autonoma de San Luis Potosi, Mexico

A. R. Barker, H. Huang, R. Niclasen, M. Wilking
University of Colorado, Boulder, Colorado, 80309

M. Campbell, R. Gustafson, M. Longo, H. Park
University of Michigan, Ann Arbor, Michigan 48109

C.M. Jenkins
University of South Alabama, Mobile, Alabama 36688

K. Lang
University of Texas at Austin, Austin, Texas 78712

C. Dukes, L. Lu, K. Nelson, G. Niculescu
University of Virginia, Charlottesville, Virginia 22901


* Spokesman: P.S. Cooper, pcooper@fnal.gov, (630) 840-2629
Web Address: www.fnal.gov/projects/ckm/Welcome.html

- Groups from 4 national labs and 6 universities
- 48 people now; 7 postdocs + students.
Will grow by $\sim 2\times$ (U. Colorado joined).
- Roots in BNL787/949, CDF, IHEP-Istra, KTeV, HyperCP, SELEX :
Substantial experience in rare K decays.

Measuring $|V_{td}|$ with $K^+ \rightarrow \pi^+ \nu \bar{\nu}$

- Theoretical errors are small and robustly estimated ($\sim 8\%$).
- Experimental Challenge:
 - $\text{Br}[K^+ \rightarrow \pi^+ \nu \bar{\nu}] = 8 \pm 3 \times 10^{-11}$ (SM)
 - BNL-E787 w/ 2 clean events $\Rightarrow \text{Br} = 16_{-8}^{+18} \times 10^{-11}$
 - Need 6 MHz K decays to collect 100 events in 2 years.
 - Need to control background to 10^{-11} of all K^+ decays & interactions.
- CKM's experimental goal:
 - 100 signal events (at $\text{Br} = 1 \times 10^{-10}$) with < 10 background in 2 years.
 - other physics: form factor, V_{us} & V_{ud} unitarity test, LFV search, χ PT tests, CPT and T -odd tests.

The CKM Apparatus



- 22 GeV/ c enriched K^+ beam: decay in flight.
- 30 MHz K^+ \Rightarrow very-high rate, low-mass detectors.
- Philosophy: Make redundant measurements with proven technologies.

CKM is similar in size and scope to KTEV

Progress Since Approval

Technical Progress:

- Prototype 13–cell superconducting RF cavity built and under test.
- Construction of prototype upstream chamber in progress.
- Construction of prototype beam time stamp fiber array in progress.
- Technical design of Beam Interaction Veto.
- Prototype vacuum veto sector built and tested in beam.
- Prototype straw chamber tested in vacuum.
- Inherited Magnet, CsI (for FVS) and Muon detectors from KTeV.
- Front-end electronics prototypes in testing.
- DAQ/Trigger design, simulation and prototyping.

Other:


- experiment has been sited
- Internal Lab (Temple) Review

Beamline

- KTeV experience:
 - Neutral K beam tails controlled and understood at the 10^{-4} level.
 - Detector rates predicted by GEANT and validated by measurement.
 - Same people designed the CKM beam line.

Extrapolation of the rate of “out-of-time” hits in KTeV
⇒ negligible low energy n background in CKM.



Enriching the Kaon Content of the Beam



	v/c
π^+	0.99998
K^+	0.99975
p	0.99909


p	K^+	π^+
7.7 cm	2.01 cm	0 cm
256 ps	67 ps	0 ps
360°	94.1°	0°

$1/256 \text{ ps} = 3.91 \text{ GHz}$



Superconducting RF Separated Beam

- Require $5 \text{ MeV}/m$ deflecting gradient
 - Have achieved in prototype 1 & 3-cell cavities
- Design requires 12 structures of 13-cell cavities
 - First prototype built and under test.




- Achieved Q_0 about 60% of spec
- Suspects identified

A production prototype RF station (2×13 -cells) planned for 2004.

K-Tracker (UMS, KEAT)

Specifications:




- Rate capability
 $0.5 - 1.0 \text{ MHz/cm}^2$
- $\sim 20 \text{ cm}$ diameter aperture.
- 0.8 mm pitch anode planes interleaved w/
cathode foil planes.



- Will perform high-rate beam test in fall 2003.


Beam Time Stamp

- Tag candidate UMS tracks with ~ 1 ns resolution
- Must handle rate of ~ 1 MHz/cm²
- Similar detectors downstream: ETP, CVP



Will perform high-rate beam test in fall 2003


Required Vacuum Veto Inefficiencies




CKM-Geant simulation of low and high E_γ regions now validated with data.

Photon Veto Technology


- 0.3% VVS prototype built.
- Instrumented with ADC's and TDC's (1MeV threshold).
- Tested at JLAB in an e^- beam.




Measuring High E_γ Inefficiency at JLAB



- Achieved $< 5 \times 10^{-6}$ inefficiency at 1 GeV
- *require* $< 3 \times 10^{-5}$




Measuring Low Energy Inefficiency at IHEP



orientation of the prototype corresponds to 90°


Sources:






- measured inefficiency $< 60\%$; study on-going.
- inefficiency spec of $< 40\%$ at 4 MeV appears achievable.

DMS: Straws in Vacuum

- Follows BNL871 design
- Each view consists of a doublet layer.
- 5 mm diam., 1 m long straws having $30\ \mu\text{m}$ kapton walls.
- expected rate 120 kHz
- operation in vacuum
 - mechanical tolerance maintained
 - diffusion rate negligible



Cosmic-ray Test of Strawtubes in Vacuum




- Upper chamber in air, lower in vacuum
- All chamber specs achieved:
 - $< 150 \mu\text{m}$ resolution and 98% efficiency.
 - negligible mechanical distortion and gas diffusion
- Wrong gas (A-CO₂ for safety)


Trigger and DAQ

- A “Software-Only” trigger is feasible.
- Front-end electronics continuously send zero-suppressed data to a computer farm. (50 GB/s)
- Interconnection by Gigabit Ethernet network switch.
- Computers run various “levels” of triggering.

Logical Design:



Physical Design:



DAQ Simulation

- Geant based MC of events with variable random pile-up of multiple events. Includes effects of showering, multiple scattering and late energy deposits due to stopped particles,,,etc
- Detector & Front-end response functions include
 - drift & fiber propagation times
⇒ phase shift w.r.t. clock
 - pulse shape and attenuation
 - zero suppression ⇒ formatted data
- Network communication
- Software Trigger algorithms.

DAQ/Trigger Test Stand at Boulder

Test stand used to generate specifications for network speed and required number of CPU's in a scalable form.



Reasonable scaling of required performance to 2007:

- ~ 800-port Gigabit Ethernet Switch
- ~ 400 “10 GHz Xeon” CPU's

Front-end Electronics Developments

- ASIC or discrete circuitry using commercial components?
 - 100 MHz QIE-vxx (ASIC) in development
 - an implementation of the QIE concept using commercial parts is also under development
 - Amplifier-shaper-discriminator from commercial components has performance comparable to UPenn ASDQ
- Time Distribution System
- FPGA-based Time Measurement Chip under development
- Sparsified data structure defined
 - used in DAQ simulations

Outcome of the Temple Review

- Technical concerns are “much reduced”
- Modest cost increase (25%) advised for Detector and SCRF systems.
- Lack of engineering resources for civil construction and conventional beamline prevents the associated costs from being accurately known now.

Recommendation: work toward a review of these items in 6 mos. with engineering support provided by the lab.

Conclusions

- Active work on Detector, DAQ/Trigger systems and SCRF
 - photon veto ineff. measurements → engineering
 - High rate testbeam for *K*-tracker, Beam Time Stamp, KRICH and Straws in 2003
 - DAQ/Trigger design, simulation and testing
 - 13-cell SCRF cavity under testing w/ plan// towards production prototype RF station in 2004.
- This will validate technology and enable accurate cost estimates for detector, DAQ and beam.
- Fermilab is providing engineering to improve accuracy of civil construction and conventional beamline costs.

Assuming favorable P5 recommendation: plan for Lehman baseline in 2004.